



City of Oceanside Building Division Information Bulletin

GREASE INTERCEPTOR TANK WITH SAMPLE BOX REQUIREMENTS

1. SIZE AND LOCATION OF INTERCEPTOR TO BE APPROVED PRIOR TO INSTALLATION.
2. INTERCEPTOR TO HAVE:
 - A. SAMPLE BOX
 - B. SANITARY TEE; INSIDE SAMPLE BOX, DISCHARGE SIDE
 - C. VENT
 - D. CLEANOUT PRIOR TO LATERAL CONNECTION
 - E. MANHOLE AT EACH INTERNAL BAFFLE – NO MORE THAN 10' BETWEEN MANHOLE
3. INSPECTION OF INTERCEPTOR
 - A. ALL CONNECTIONS TO INTERCEPTOR TO BE INSPECTED BY CITY INSPECTOR PRIOR TO BACKFILL
 - B. INTERCEPTOR TO BE FILLED WITH WATER PRIOR TO INSPECTION, PER MANUFACTURER'S INSTRUCTIONS OR REQUEST
4. ALL MANHOLES AND SAMPLE BOXES TO BE INSTALLED A MINIMUM OF 1/2" ABOVE FINISH GRADE/PAVEMENT WITH A CONCRETE COLLAR A MINIMUM OF 18" ROUND ALL MANHOLE LIDS AND 12" DEEP
5. CONCRETE COLLAR, SAMPLE BOX FITTING AND ALL EXTERIOR PIPING SUPPLIED BY INSTALLER
6. A SOILS INSPECTION REPORT IS REQUIRED BY A STATE LICENSED GEOTECHNICAL SOILS ENGINEER WITH A MINIMUM 95% COMPACTION WHEN INSTALLED IN TRAFFIC AREA

NOTE: The Grease Interceptor shall be sized using the current California Plumbing Code

Minimum size shall be 750 Gallons

