



**NOTES**

1. SEWAGE BACKWATER VALVE ASSEMBLY TO BE INSTALLED ON ALL LATERALS WHERE THE FINISH FLOOR OR PAD ELEVATION IS LOWER THAN THAT OF THE FIRST UPSTREAM MANHOLE.
2. PROPERTY OWNER IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF THE SEWAGE BACKFLOW VALVE ASSEMBLY.

Revision	By	Approved	Date
06/05/01	DW		
10/18/02	DW		
08/06/04	AC		
01/04/16	MU		
07/01/17	SM		08/01/17

**CITY OF OCEANSIDE**

**SEWAGE BACKWATER VALVE ASSEMBLY**

*Steven E. Strapac* 9/17/17  
 CITY ENGINEER Date  
 STANDARD DRAWING NO. **S-4**