

SECTION 01043 – COORDINATION WITH AGENCY’S OPERATIONS

PART 1 - GENERAL

1.1 MAINTENANCE OF EXISTING FACILITIES/CONDITIONS

- A. During the CONTRACTOR’S performance of the work contained in these Contract Documents, precautions shall be taken to assure that no damage or unscheduled shutdowns occur to any facilities, including piping, utilities, traffic signals, roads, and structures, that are to remain in operation and are not to be modified or replaced. It is the CONTRACTOR’S responsibility to contact Underground Service Alert of Southern California (a.k.a. DigAlert) online at DigAlert Express or call 8-1-1 prior to any excavation for verification and location of utilities and notification of commencement of work. Any temporary facilities, materials, equipment and labor required to achieve this objective shall be provided by the CONTRACTOR at its own expense. At the completion of work, all such temporary facilities, materials and equipment remaining shall be removed from the site.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- A. Section 01039 – Coordination and Meetings
- B. Section 01047 – Connections to Existing Facilities
- C. Section 01170 – Special Technical Provisions

1.3 ORDER OF THE WORK

- A. The work shall be carried on at such places on the project and also in such order or precedence as may be found necessary by the CONTRACTOR to expedite the completion of the project with due consideration for AGENCY’S operations. After work has begun on any portion or designated part of the project, it shall be carried forward to its final completion. The AGENCY has the right to change the precedence of work as needed to maintain the AGENCY’S operation.

1.4 SHUTDOWNS

- A. All shutdowns shall comply with the provisions of the Oceanside Water Utilities Manual.
- B. Any proposed shutdowns must be indicated on the CONTRACTOR’S preliminary schedule to be submitted for review by the AGENCY at the Preconstruction Meeting. The actual allowable durations of the shutdowns will be determined during the preparation of the detailed construction schedule.
- C. The CONTRACTOR shall compile a detailed list of all items of work which must be accomplished during any shutdown. The CONTRACTOR shall coordinate his work to minimize the required number of shutdowns by accomplishing as many tasks as possible during each shutdown period. The CONTRACTOR shall submit this list of items to the AGENCY as a part of the construction schedule.

SECTION 01043 – COORDINATION WITH AGENCY’S OPERATIONS

- D. The schedule shall indicate all periods and duration of each proposed shutdown and the items of work which will be accomplished, unless otherwise specified herein or noted on the drawings. The CONTRACTOR shall make specific written requests for all shutdowns in advance of the proposed shutdown for review and approval by the AGENCY in accordance with the provisions of the Oceanside Water Utilities Manual. The written request shall include a complete detailed plan of the CONTRACTOR’S proposed activities including schedule, manpower, equipment, materials and methods which will be utilized to perform the required work during the proposed shutdown. Should the AGENCY feel that the CONTRACTOR’S proposed plan is insufficient to successfully complete the required work during the period of the shutdown, the CONTRACTOR shall make the appropriate revisions in his proposed plan to the satisfaction of the AGENCY.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

****END OF SECTION****