

## **SECTION 01047 – CONNECTIONS TO EXISTING FACILITIES**

### **PART 1 – GENERAL**

#### **1.1 WORK OF THIS SECTION**

- A. Perform all construction necessary to complete connections and tie-ins to existing facilities under AGENCY observation.
- B. Keep existing facilities in operation, unless otherwise specifically permitted in these Specifications or approved by the AGENCY.
- C. CONTRACTOR shall perform all construction activities so as to avoid interference with operations of the facility and the work of others.
- D. CONTRACTOR shall provide sub surface investigations for locating and field verifying all existing piping, structures and equipment affected by the work. All sub surface investigations shall be performed by the CONTRACTOR at no additional cost to the AGENCY. Delays in the work, as a result of insufficient sub surface investigations, will be solely the CONTRACTOR'S responsibility. No time extensions will be allowed for work that is delayed as a result of insufficient sub surface investigations and field verification.

#### **1.2 SEQUENCING AND OPERATIONS**

- A. Insofar as possible, all equipment shall be tested and in operating condition before the final tie-ins are made to connect equipment to the existing facility.
- B. CONTRACTOR shall carefully coordinate all work and schedules and shall provide AGENCY written requests for all shutdowns in advance of the proposed shutdown for review and approval by the AGENCY in accordance with the provisions of the Oceanside Water Utilities Manual.

#### **1.3 REFERENCE SPECIFICATIONS, CODES, AND STANDARDS**

- A. The City of Oceanside Water, Sewer, Recycled Water Design & Construction Manual (Water Utilities Manual).

#### **1.4 SUBMITTALS**

- A. Submit detailed schedule of proposed connections, disconnections, and reconnections, including laterals, listing sequence and durations of all activities including shutdowns and tie-ins. The detailed schedule must be submitted by the CONTRACTOR and approved by the AGENCY prior to the "Request for Shutdown" being submitted.

### **PART 2 – MATERIALS (NOT USED)**

**SECTION 01047 – CONNECTIONS TO EXISTING FACILITIES**

**PART 3 – EXECUTION (NOT USED)**

**\*\*END OF SECTION\*\***